

PCS Door Access PHS/JH - Addendum 5/8/2017

- 1) New doors that will be installed at a later date, provide controllers but not door hardware.
 - a) PHS Door 3A qty 1 Single Door to be cut into brick wall,
 - b) PHS Office qty 2 Single Door each hall to be added later,
 - c) PJHS Office Near Door 2 Qty 2 Single Door each hall to be added later.
- 2) "A proper accredited lock-smith will install/modify all door hardware" change to "A proper accredited lock-smith or door installation vendor will install/modify all door hardware"
- 3) RTE means interior card reader.
- 4) Interior signage will be by the school district.
- 5) If required to provide the necessary number (6) total with existing and new license than provide a total of 2 tokens.
- 6) District will provide 120v access in technology closets as needed.
- 7) P225XSF Reader may be substituted where appropriate over P325XSF readers.
- 8) Quick disconnects allowed and required in locations with removable mullions.
- 9) Ability for secretaries at both PJHS [door 2] and PHS [door 3] to manually allow access in from their work areas. Two locations at PJHS and one location at PJHS.
- 10) Our current Kantech Version is 6.0.4.

PHS Changes as discussed:

1. Door 3 - Are 2 door leafs being controlled or just 1? **[2 door leafs are being controlled]**
2. Door 3 - RTE on interior doors? **[No]**
3. Door 3 - ada door operator? **[Leave ADA at current location not controlled by door access]**
4. Door 4 - ada door operator **[Leave ADA at current location not controlled by door access]**
5. Door 5A? **[Add sensor and alarm]**
6. Door 7A? **[Add sensor and alarm]**
7. Door 12? **[Sensor and alarm]**
8. Band and Choir doors? **[Add sensor, no alarm]**
9. Kitchen Door 14A? **[No sensor, no alarm]**
10. Loading Dock Door 14? **[No sensor, no alarm]**
11. Door 15A? **[Add sensor, alarm]**
12. Boiler Room Door? **[No sensor, no alarm]**

JH Changes as discussed:

1. Boiler Room door (9A)? **[No sensor, no alarm]**
2. Coiling Door at Loading Dock(5A)? **[No sensor, no alarm]**
3. Door to Electric Room (5B)? **[No sensor, no alarm]**
4. Door 7 RTE? **[Add RTE reader for staff]**
5. Door 9? **[No reader, sensor and alarm only]**
6. Door to Boiler Room (9A)? **[no sensor, no alarm]**
7. Door 1 and 1A? **[Add Sensor to door 1A; CHANGE DOOR 1 TO Single door right access]**
8. Door 3/ada operator/no conduit to pedestal? **[Use wireless reader for door access near ADA operator]**
9. Door 3 controll all doors?**[Control all 4 doors]**